

SCOPE OF WORK

Contractors are required to furnish all mobilization, labor, materials, equipment, tools, signage, traffic control, and other incidentals necessary to apply TYPE II slurry seal to approximately 30,112 square yards of paved roadway located throughout the Town of Frisco. The TYPE II slurry seal shall contain aggregate of dark nature and strictly adhere to ISSA standards for TYPE II slurry seal. The contractor is required to notify all businesses and residents located within the work area prior to the project start date. The contractor shall supply all signage and traffic control, which must confirm to the most recent MUTCD standards. The contractor is responsible for masking over all valve covers, manholes, crosswalk bars, and stop bars where slurry seal is to be applied. A bid alternative for slurry seal to be applied to an additional 14,513 square yards of roadway is to be included with the submitted bid. All work is to be completed on or before September 3rd.