

## INVITATION TO BID

Notice is hereby given that the Town of Frisco (the "Town") will receive sealed bids for Asphalt Mill and Overlay on 1<sup>st</sup>, 2<sup>nd</sup>, 5<sup>th</sup>, 6<sup>th</sup> and 7<sup>th</sup> Avenues until, Friday, April 1, 2022, at 12 p.m.

The Town reserves the right to reject any and all bids, and to make final determination in the event of duplications.

No bid may be withdrawn for a period of sixty (60) days after the date set for opening thereof.

There will be a pre-bid meeting on Thursday, March 24<sup>th</sup>, 2022 at 10 a.m. The meeting will be conducted at 1 East Main Street (Frisco Town Hall), Frisco, CO 80443.

Colorado labor shall be employed to perform the work for which bids are requested herein to the extent of not less than eighty percent (80%) of each type or class of labor in the several classifications of skilled and common labor employed on such work, pursuant to C.R.S. § 8-17-101.

**[The Town requires that a certified or cashier's check be deposited or that a corporate surety bond in the amount of five percent (5%) of the total bid amount be provided before the Town can accept or consider any bid.]** The bid **[and the deposit or bond]** shall be filed with the Town Clerk, securely sealed and endorsed on the outside with a brief statement as to the nature of the item or work for which the bid is provided. **[Upon a bid award, such deposit or bond shall be returned to the unsuccessful bidder(s). In the case of the successful bidder, the deposit or bid bond will be returned upon receipt of the required payment and performance bonds, each in the full amount of the contract price.]**

Bids will be opened publicly at 12 p.m. on Friday, April 1, 2022, at 102 School Road, Frisco, CO 80443, and shall be tabulated by the Town.

Any questions regarding the project should be directed, in writing, to Landon Sengelman, Project Manager, at the following e-mail address: [LandonS@townoffrisco.com](mailto:LandonS@townoffrisco.com).

Bid results are usually available one hour after bid opening and can be received by emailing Landon Sengelman, Project Manager, at [LandonS@townoffrisco.com](mailto:LandonS@townoffrisco.com).



# Town of Frisco

## Public Works Department

P.O. Box 4100 • Frisco, Colorado 80443

### TOWN OF FRISCO REQUEST FOR PROPOSALS

The Town of Frisco is accepting proposals for Asphalt Mill and Overlay on 1<sup>st</sup>, 2<sup>nd</sup>, 5<sup>th</sup>, 6<sup>th</sup> and 7<sup>th</sup> Avenues on Main Street.

All proposals are due no later than 12PM on Friday, April 1st, 2022.

All proposals shall either be mailed to the Town of Frisco PO Box 4100, 102 School Road; Frisco, CO 80443, hand delivered, or emailed to [landons@townoffrisco.com](mailto:landons@townoffrisco.com).

#### Scope of Work:

- Mobilization
- Traffic Control
- Removal of asphalt mat includes saw cuts
- Adjust Man hole cover
- Aggregate Base course (class 6)
- 2" asphalt mill
- 2" asphalt overlay
- Parking space striping
- Handicap spaces painted
- Inlay and installation of 24" crosswalk thermoplastics
- Inlay and installation of 12" stop bar thermoplastics

Nothing herein shall require the Town of Frisco to accept any proposal, and the Town of Frisco reserves the right to reject any or all proposals. The proposals shall remain open and not withdrawn for a period of 45 (forty-five) days from the date designed for its due date.

(970) 668-0836 • Fax: (970) 668-1327 • [FriscoGov.com](http://FriscoGov.com)

<b>1<sup>st</sup> Ave Main Street to Galena Alley</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	10,080		
4	Asphalt 2" Overlay	TON	123.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	455		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap spots	Spots	2		
<b>1<sup>st</sup> Ave Galena Alley to Galena St</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	3840		
4	Asphalt 2" Overlay	TON	47.00		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	0		
7	Striping	LF	0		
8	Adjustments of valve boxes and man holes as needed	EA	1		

1 <sup>st</sup> Ave Main Street to Granite Alley					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	10,080		
4	Asphalt 2" Overlay	TON	123.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	490		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	1		
1 <sup>st</sup> Ave Granite Alley to Granite St					
Item No.	Item Description	Units	Quantity	Unit Price	Item Cost
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	4,800		
4	Asphalt 2" Overlay	TON	59.00		
5	12" Stop Bar	SF	18		
6	24" Crosswalk	SF	0		
7	Striping	LF	0		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	1		

<b>2nd Ave Main Street to Granite St</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	19,710		
4	Asphalt 2" Overlay	TON	241.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	1,198		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	1		
<b>N. 5<sup>th</sup> Ave Main Street to Galena Alley</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	9,180		
4	Asphalt 2" Overlay	TON	112.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	590		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap spots	Spots	2		

<b>S. 5<sup>th</sup> Ave Main Street to Granite Alley</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	10,080		
4	Asphalt 2" Overlay	TON	123.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	140		
7	Striping	LF	716		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	2		
<b>S. 5<sup>th</sup> Ave Granite Alley to Granite St.</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	6,125		
4	Asphalt 2" Overlay	TON	66.00		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	0		
7	Striping	LF	0		
8	Adjustments of valve boxes and man holes as needed	EA	1		

<b>N. 6<sup>th</sup> Avenue Main Street to Galena St.</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	20,496		
4	Asphalt 2" Overlay	TON	251.000		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	453		
8	Adjustments of valve boxes and man holes as needed	EA	1		
<b>S. 6<sup>th</sup> Ave Main Street to Granite St.</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	19,440		
4	Asphalt 2" Overlay	TON	238.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	1,291		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	2		

**N. 7<sup>th</sup> Avenue Main Street to Galena Alley**

<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	9,720		
4	Asphalt 2" Overlay	TON	119.0		
5	12" Stop Bar	SF	0		
6	24" Crosswalk	SF	100		
7	Striping	LF	457		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	1		

**S. 7<sup>th</sup> Avenue Main Street to Granite St.**

<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Asphalt removal 2"	SF	18,900		
4	Asphalt 2" Overlay	TON	231		
5	12" Stop Bar	SF	18		
6	24" Crosswalk	SF	100		
7	Striping	LF	1326		
8	Adjustments of valve boxes and man holes as needed	EA	1		
9	Handicap Spots	Spots	2		



Scope of Work:	Units	Totals:	Price:
Mobilization	LS	1	
Traffic Control	LS	1	
Asphalt removal 2" Mill	SF	142,451	
Asphalt 2" Overlay	TON	1733.000	
12" stop bar	SF	36	
24" crosswalk	SF	940	
Striping	LF	6976	
Adjustments as needed	EA	12	
Handicap Spots	SPOTS	14	