



Town of Frisco

Public Works Department

P .O. B ox 4100 • Frisco, Colorado
80443

TOWN OF FRISCO REQUEST FOR PROPOSALS

The Town of Frisco is accepting proposals for bridge repair on the following bridges: West Main St., Creekside Dr., Madison Ave. and 4th Ave. This work will be completed in 2023. This work will be completed by October 31, 2023. If this work cannot be completed by that date, the prospective bidder shall provide an alternative schedule and justification for their timeline. A mandatory site walk - through will occur on November 10th 2022 at 10am. Questions will be due November 22nd 2022 and answered December 2nd 2022. All proposals are due no later than 12:00 pm December 13th 2022. All proposals shall be mailed, hand delivered to the Town of Frisco PO Box 4100, 102 School Road; Frisco, CO 80443 or emailed to landons@townoffrisco.com.

Scope of Work:

- Mobilization
- Traffic Control
- Raise approach and bridge rail
- Seal crack and raveling in asphalt abutments
- Install scour counter measures at exposed piles at abutments
- Repair scaled Wingwalls
- Repair spalls in culvert walls
- Seal and place overlay
- Seal concrete deck
- Patch spalls in girders
- Grind smooth or feather patch settled sidewalk
- Install double nested flex beam at rail transition
- Remove and reapply chip seal at peeled location
- Reseal cracks in asphalt at approaches and repair asphalt at approaches

Nothing herein shall require the Town of Frisco to accept any proposal, and the Town of Frisco reserves the right to reject any or all proposals. The proposals shall remain open and not withdrawn for a period of 45 (forty-five) days from the date designed for its due date.

(970) 668-0836 • Fax: (970) 668-1327 • FriscoGov.com

West Main St.

Item Number	Item Description	Units	Quantity	Unit Price	Item Costs
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
4	Raise approach rail	LF	250		
5	Raise bridge rail	LF	210		
6	Seal crack and raveling in asphalt at abutments	LF	100		
7	Install scour counter measures at exposed piles at abutments	EA	2		

Creekside Dr.

Item Number	Item Description	Units	Quantity	Unit Price	Item Costs
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
8	Repair Scaled Wingwalls	CY	111.11		
9	Repair spalls in culvert walls	CY	426.66		
10	Grind top slab	SY	178.88		
11	Seal and place overlay	SY	178.88		

Madison Ave.

Item Number	Item Description	Units	Quantity	Unit Price	Item Costs
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
12	Seal Concrete Deck or apply waterproof membrane and pave with 2" of asphalt	SY	238		
13	Patch Spalls in Girders	LS			

4th Ave.

Item Number	Item Description	Units	Quantity	Unit Price	Item Cost
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
14	Grind smooth or feather patch settled southwest sidewalk	SY	40		
15	Install double nested flex beam at SE rail transition	LF	15		
16	Remove and reapply chip seal at peeled location	SY	248.88		
17	Reseal cracks in asphalt at approaches and repair asphalt at south approach	TON	13.68		