

# Addendum



Date: 11/14/2022

Addendum No.: 1

Project: 2023 Mill and Overlay

Summary: This addendum will correct the following:

- The amount of EV charging thermoplastic symbols on S. 3<sup>rd</sup> Ave Main St. to Granite St. from 1 to 3
- The addition of a " concrete pan on S. 3<sup>rd</sup> Ave Main St. to Granite St. (The concrete will be cut and pulled by the Town of Frisco at the start of the scheduled project)

The corrections will be updated on the bid tabulation and RFP



# Town of Frisco

## Public Works Department

P.O. Box 4100 • Frisco, Colorado 80443

### TOWN OF FRISCO REQUEST FOR PROPOSAL

The Town of Frisco is accepting proposals for Asphalt Mill and Overlay on: Belford Street (Peak One), Dam Road, N. 3<sup>rd</sup> Ave Main St to Galena St, N. 3<sup>rd</sup> Ave Galena Dead End, S. 3<sup>rd</sup> Ave Main St. to Granite St, N. 4<sup>th</sup> Ave Main St to Galena Alley, N. 4<sup>th</sup> Ave Galena Alley to Creekside Drive and S. 4<sup>th</sup> Ave Main St. to Granite St. All work will be done in 2023. A mandatory site visit will be held on November 8<sup>th</sup> 2022 at 10:00 AM at 1 Main Street Frisco, Co 80443. Questions will be due November 15<sup>th</sup> 2022 and answered November 22<sup>nd</sup> 2022.

All proposals are due no later than 11:00 AM December 6th, 2022.

All proposals shall be mailed or hand delivered to the Town of Frisco PO Box 4100, 102 School Road; Frisco, CO 80443 or emailed to [landons@townoffrisco.com](mailto:landons@townoffrisco.com).

#### Scope of Work:

- Mobilization
- Traffic Control
- Removal of asphalt mat includes saw cuts
- Adjust Man hole cover
- Aggregate Base course (class 6)
- 2" asphalt mill
- 2" asphalt overlay
- Parking space striping
- Road striping of double yellow and white lines
- Handicap spaces painted
- Inlay and installation of 24" crosswalk thermoplastics
- Inlay and installation of 18" stop bar thermoplastics
- Inlay and installation of straight right, left turn and right turn thermoplastics
- Installation of EV charging thermoplastic symbol

#### **Installation of 8" Concrete Pan**

Nothing herein shall require the Town of Frisco to accept any proposal, and the Town of Frisco reserves the right to reject any or all proposals. The proposals shall remain open and not withdrawn for a period of 45 (forty-five) days from the date designed for its due date.

<b>Dam Road</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	120,430		
2	Asphalt 2" Overlay	TON	1,471.9		
3	18" Stop Bar	SF	81		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	2,695		
6	Striping White	LF	550		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		
9	Thermoplastics- straight right	EA	2		
10	Thermoplastics- right turn	EA	2		
11	Thermoplastics- left turn	EA	4		

<b>N. 3<sup>rd</sup> Ave Main St. to Galena St.</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	18,846		
2	Asphalt 2" Overlay	TON	230.54		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	1,364		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	2		

<b>N. 3<sup>rd</sup> Ave Galena Dead End</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	4,704		
2	Asphalt 2" Overlay	TON	57.49		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	0		
6	Striping White	LF	0		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

<b>S. 3<sup>rd</sup> Ave main St. to Granite</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	19,276		
2	Asphalt 2" Overlay	TON	235.62		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	1,185		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	3		
11	EV charging space	Spots	<del>1</del> 3		

<b>N. 4th Ave Main St. to Galena Alley</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	9,976		
2	Asphalt 2" Overlay	TON	121.92		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	500		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

<b>N. 4<sup>th</sup> Ave Galena Alley to Creekside Drive</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	15,120		
2	Asphalt 2" Overlay	TON	184.8		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	0		
5	Striping Yellow	LF	0		
6	Striping White	LF	60		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

<b>School Road</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	26,494		
2	Asphalt 2" Overlay	TON	291.45		
3	18" Stop Bar	SF	36		
4	24" Crosswalk	SF	200		
5	Striping Yellow	LF	810		
6	Striping White	LF	155		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		
10	Thermoplastics- right turn	EA	2		
13	Thermoplastics- straight left	EA	2		

<b>S. 4<sup>th</sup> Ave Main Street to Granite Street</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	17,211		
2	Asphalt 2" Overlay	TON	210.35		
3	18" Stop Bar	SF	18		
4	24" Crosswalk	SF	100		
5	Striping Yellow	LF	0		
6	Striping White	LF	718		
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	1		

<b>Belford Street</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	15,700		
2	Asphalt 2" Overlay	TON	191.88		
3	18" Stop Bar	SF	0		
4	24" Crosswalk	SF	36		
5	Striping Yellow	LF	0		
6	Striping White	LF			
7	Adjustments of valve boxes and man holes as needed	LS			
8	Handicap spots	Spots	0		

<b>Totals:</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Units</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Item Cost</b>
1	Asphalt removal 2" Mill	SF	222,953		
2	Asphalt 2" Overlay	TON	2,995.95		
3	18" Stop Bar	SF	189		
4	24" Crosswalk	SF	636		
5	Striping Yellow	LF	3,505		
6	Striping White	LF	4,322		
7	Adjustments of valve boxes and man holes	LS			
8	Handicap spots	Spots	6		
9	Thermoplastics- straights right	EA	2		
10	Thermoplastics- right turn	EA	4		
11	EV charging space	EA	<del>1</del> 3		
13	Thermoplastics- straight left	EA	2		
14	Mobilization	LS	1		
15	Traffic Control	LS	1		
16	Concrete pan installation	SF	1,080		